



Conduits and cables must run outside drilling zones and be buried sufficiently deep (minimum 15 cm).

*All the cables go to the motor of the first leaf to open.